

**Name of the work: Providing Polycarbonate sheet over existing M.S frame works
at Sugandi and Gulabi connecting corridors of CB Site Housing**

Schedule of Quantities

Sl. No.	Description of work	Unit	Qty	Rate	Amount
				In figures & words	
1	Providing and fixing 10mm thick multi-walled translucent polycarbonate sheet (Lexan) fixed to purlin box section/above pergola section to a line, gradient with aluminium beadings of 50x4mm thick to the joints with self driven screw, sealent, edges covered with 12mm thick aluminium channels etc., complete all as per specification and as directed by E-IN-C etc., complete.	Sqm	65.00		
Total Amount Rs.					
Note:- The contractor shall quote his rates in this schedule of quantities. Submission of tender in any tother format is liable for rejection.					

Total amount in words:-

Signature of the contractor:

Date:

Address:

Seal: