

Name of the work - Providing PVC flooring for Sub-station at NCBS Campus

Schedule of Quantity

SL.No	Description	Units	Quantity	Rate in Figures	Amount
1	Providing and laying unbacked flexible P.V.C / marblex flooring / skirting with PVC sheets / Marblex tiles as specified below of approved make and shade including preparing the surface, cleaning as required and applying adhesive - as recommended by the PVC / Marblex tile manufacturers, laying, aligning, cutting in required size and pattern, trimming of tiles, removing the adhesive stains on the surface including cleaning the surface with soap solution (2 table spoons of soap powder for 5ltr of water) using a cloth or mop or and wiping the dried surface with soft dry cloth etc; complete all as per specifications.In PVC flooring / skirting / dadoing: with 2mm thick unbacked flexible fully homogeneous PVC sheets in rolls of approved make and quality - viz., Poly floor of M/s. Poly floor vinyl flooring or TUSKER of M/s. Krishna vinyls Limited or Birla vinoleum of M/s. Birla corporation Limited or equivalent make conforming to IS: 3462-1986.	Sqm	126.00		
	Rate in Words				
	Total Amount				

Note: The contractor shall quote his rates in this schedule of quantities.

Total amount in Words:

Signature of the Contractor:

Date:

Address: