

Name of the work: - Setting up of Cryo Facility in Basement Floor Instem lab-Vinyl flooring work.

Schedule of Quantity

SL. No.	Description	Unit	Qty	Rate	Amount
1	Providing and fixing of Gerflor or equivalent range of approved colour and shade of homogeneous vinyl floors of size 200 cmx20m x 2.00 mm with:Static electrical propensity < 2.0, wear resistance < 2.0 mm ³ , Residual indentation of ~0.02mm, colour fastness of stage < 6 mm,thermal conductivity 0.25W/(m.K) and Anti-bacterial activity < 99% inhibits growth.. Gerflor Lab grede vinyl floor should be installed on a smooth , hard and absolutely leveled sub floor. . Clean the floor with a liquid detergent diluted with warm water stubborn marks can be removed with a fine abrasive powder and scouring pad. Rinse properly with clean water to remove all traces of detergent. Polishing or surfaces coatings on Lab grade floors must not be used as these will leave a film over the floor surface which will alter the conductivity of the installation., including skirting.	sqm	170.00		
	Rate in Words				
2	Providing and laying 3 mm thick self levelling compound of level 0 / Ardex or equivavlent for the base of vinyl flooring as per manufactures specifications and as directed by E-In-C etc., complete.	sqm	130.00		
	Rate in Words				
					Total Rs.

Note: The contractor shall quote his rates in this schedule of quantities. Submission of tender in any other format is liable for rejection.

Total amount in Words:-

Signature of the contractor:-

Date:-

Address: