

**Name of Work: Providing & Fixing Aluminum Cladding for Existing Nitrile Foam
Tubed GI Hot Water Line at SLC Terrace**

Schedule of Quantity

Sl. No.	Description of work	Unit	Qty	Rate	Amount
1	Providing and fixing Aluminum cladding of 26 guage for existing NBR tubed GI hot water supply line -				
a.	For 40mm dia pipe - aluminium cladding should be 215mm outer dia	Rmt	55.00		
b.	For 25mm dia pipe - aluminium cladding should be 165 mm outer dia	Rmt	55.00		
c.	For 20mm dia pipe - aluminium cladding should be 115 mm outer dia	Rmt	20.00		
	Rate in Words				
				Total Amount Rs.	

Note: The contractor shall quote his rates in this schedule of quantities.

Total amount in Words:

Signature of the Contractor:

Date:

Address: